

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

0000
 API NUMBER 15-189-20321-

LEASE NAME Arco-Davis

WELL NUMBER #2

SPOT LOCATION 660' FNL & 660' FEI

SEC. 24 TWP. 32 RGE. 35 (E) or (W)

COUNTY Stevens

Date Well Completed 4-27-77

Plugging Commenced 11-1-1987

Plugging Completed 11-4-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Claassen Exploration Co.
 ADDRESS 427 S. Boston, Suite 1901, Tulsa, OK 74103

PHONE # (918) 599-0409 OPERATORS LICENSE NO. 04957

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? _____

Which KCC/KDHE Joint Office did you notify? yes

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Chester Depth to top 6024' bottom 6122' T.D. 6200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	1715'	0'
Production				5 1/2"	6200'	2722'
Chester	Oil	6108	6142			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pump 2 sks. Hulls & 25 sks. cement at 2700' - Pressured to 1000 lbs. - Mud 2600' to 1750'
Pump 50 sks. cement 1750' to 1650' - Mud 1650' to 650'
Pump 25 sks. cement 650' to 575' - Mud 575' to 40'
Put bridge and 10 sks. cement 40' to 0'
Cut off 8 5/8" 3' below ground level & cap.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
 Address Box F, Sublette, Ks, 67877

STATE OF Kansas COUNTY OF Stevens ~~Haskell~~ Haskell, ss.

I, Edgar J. Eves (~~XXXXXXXXXXXXXXXXXXXX~~) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

11-23-87 (Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks, 67877
 RECEIVED
 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 16th day of Nov., 1987



NOV 23 1987
Sondra L. Eves
 Notary Public

My Commission expires: 12-6-88

CONSERVATION DIVISION
 Wichita, Kansas