

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

0000

API NUMBER 15-189-20,225-

LEASE NAME Arco-Davis

WELL NUMBER 1

SPOT LOCATION 660' FNL 1980'

SEC 24 TWP 32 RGE 35 <sup>FEL</sup> (X) or (W)

COUNTY Stevens

Date Well Completed 4-20-75

Plugging Commenced 10-27-1987

Plugging Completed 10-30-1987

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Claassen Exploration Co.  
ADDRESS 427 S. Bosten, Suite 1901 Tulsa, OK 74103

PHONE # (918) 599-0409 OPERATORS LICENSE NO. 04951

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes if not, is well log attached? \_\_\_\_\_

Producing formation Chester Depth to top 6079' bottom 6114' T.D. 6198'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	1716'	0'
Production				5 1/2"	6193'	2645'
Chester	Oil	6080	6120			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pumped 2 sks. hulls & 25 sks. cement to 5800' - pressured to 1000 lbs. - Pumped 25 sks. cement at 2600' Mud - 2500' to 1750' - Pumped 50 sks. 1750' to 1650' Mud to 650' Pump 25 sks. cement 650' to 575' - Mud 575' to 40' Bridge and 10 sks. cement 40' to 0' - Cut off 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497  
Address Box F, Sublette, Ks, 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (XXXXXXXXXXXXXXXXXXXX) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves  
(Address) Box F, Sublette, Ks, 67877



SUBSCRIBED AND SWORN TO before me this 16th day of Nov., 19 87

Sondra L. Eves  
Notary Public

My Commission expires: 12-6-88

NOV 23 1987