

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stevens

County. Sec. 24 Twp. 32 Rge. 35W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW/4 SW/4

Lease Owner Northern Natural Gas Producing Co.

Lease Name Boles "G" Well No. 1

Office Address 2223 Dodge St., Omaha, Nebraska

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 11 19 56

Application for plugging filed August 11 19 56

Application for plugging approved August 11 19 56

Plugging commenced August 11 19 56


Plugging completed August 11 19 56

Reason for abandonment of well or producing formation oil in commercial quantities not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 6265' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	589'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with extra heavy rotary mud from total depth (6265') to 2950'. Set Plug #1 with 150 sacks cement from 2950' to 2500'. Mud from 2500' to 575'. Set Plug #2 with 35 sacks cement from 575' to 540'. Filled hole with extra heavy rotary mud from 540' to 20'. Set Plug #3 with 15 sacks cement. Steel plate welded on surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.

Address 814-16 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

R. R. McNicol (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. CAPITT DRILLING, INC.

(Signature) RR McNicol

814-16 Union Center, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1956

My commission expires Sept. 30, 1959

Notary Public. [Signature]

PLUGGING
FILE SEC 24 T 32 R 35W
BOOK PAGE 89 LINE 5

ED MISSION
8-17-56
CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLING LOG

OPERATOR: Northern Natural Gas Producing Co. CONTRACTOR: Capitt Drilling, Inc.
 Boles "G" #1 COMM: 7/5/56
 C SW/4 SW/4 Sec. 24-32S-35W COMP: 8/11/56
 Stevens County, Kansas

Formations;

Shale	60'
Sand	68'
Shale	75'
Shale Sand	140'
Sand	165'
Shale Clay	380'
Sand	440'
Shale	540'
Red Shale	565'
Red Shale & Lime	602'
Red Bed	1110'
Lime Redrock Shells	1220'
Red Rock	1410'
Shale Lime Sand	1625'
Lime & Shale	1760'
Shale Anhydrite Lime	2400'
Shale Lime	2499'
Shale & Lime	2875'
Lime (Cherty) Shale	2945'
Lime Shale	2995'
Cherty Lime & Shale	3190'
Lime	3402'
Chalky Lime	3455'
Lime	4125'
Lime & Shale	4160'
Core #1 & 2	4279'
Lime	4358'
Lime Shale	4455'
Lime	5397'
Lime & Shale	5675'
Shale	5679'
Cored hole	5918'
Lime	6105'
Lime & Sand	6128'
Cored hole	6178'
Lime	6265'

Rotary Total Depth(D&A) 6265'.

Remarks: Set 13-3/8" surface casing
 at 589' cemented with 600 sacks
 Pozmix, 2% C.C.

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

CAPITT DRILLING, INC.

R. R. McNicol
 R. R. McNicol

REC'D
 STATE GEOL. DEPT.

AUG 17 1956

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING	
FILE SEC. 24 T. 32 R. 35W	
BOOK PAGE 89 LINE 5	