

STATE OF KANSAS
STATE CORPORATION COMMISSION
208 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21,351-0000

LEASE NAME Mueller Trust

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-28

4620 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SEC. 28 TWP. 32 RGE. 35 or W

COUNTY Stevens

Date Well Completed 8-26-89

Plugging Commenced 7-11-90

Plugging Completed 7-11-90

The plugging proposal was approved on _____ (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well loc. attached? _____

Producing Formation Council Grove Depth to Top _____ Bottom T.D. 6441

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

JUL 23 1990

Formation	Content	From	To	Size	Put In	Pulled Out
		0	1729	8-5/8"	1729'	None
			3164	5-1/2"	3164'	1350'

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Set CIBP @ 2502'. Place 3 sx cement on top of plug. Cut 5-1/2" casing @ 1350'. Circulate hole w/gel. Place 50 sk plug @ 1340'. Place 40 sk plug @ 702'. Place top plug @ 40' to surface w/15 sx cement. Use 60-40 Pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John Roger McCoy

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Roger McCoy

(Address) 110 S. Main, Suite 500
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19 90



Deborah Ann Paulus
Notary Public

Commission Expires: 1-8-92