


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-189-00110-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stevens

County. Sec. 33 Twp. 32 Rge. 35 (E) (W)

Location as "NE/CNW/SW" or footage from lines 330' offset C end SW 1/4

Lease Owner Northern Natural Gas.

Lease Name De Camp

Well No. "A" #1

Office Address Hugoton, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed yes _____ 19__

Application for plugging approved yes _____ 19__

Plugging commenced 1-22-60 _____ 19__

Plugging completed 1-24-60 _____ 19__

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes _____

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2773 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"		819'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 1-22-60. Plugging completed 1-24-60.
Plugged off bottom with sand to 2711' and dumped 25 sacks of cement
2711' to 2636' on 1-21-60 when removing tubing. Measured in on plug
2636'. Loaded hole with water. Worked pipe. Shot pipe. Shot 7"
casing at 829'. Pulled and laid down casing. Plugged well with mud;
Mudded to 560'. Set 10' rock bridge, 560'-550'. Dumped 30 sacks of
cement on rock bridge, 550'-460'. Mudded hole to 40'. Set 10' rock
bridge, 40' -30'. Capped the well with 10 sacks of cement, 30' -0'.

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of February, 19 60

My commission expires December 8th, 1963

Kayann Jenkins
Notary Public.



DeCAMP #1

Rigged up Rotary Tools 14-30-45

Set 21 jts. 10 3/4" Casing set @ 661'
Cement W/200 sx.

Tore Down Rotary Tools 5-15-45

Set 2664' of 7" Casing Cement W/900 sx.

FORMATION	FROM	TO
Sand & Gravel	0	505
Redbed	505	704
Red Sand	704	865
Shale & Sand	865	1540
Shale & Lime	1540	1760
Shale & Gyp	1760	2424
Gyp & Shells	2424	2490
Lime & Anhy	2490	2623
Lime	2623	2721
Shale	2721	2736
Lime	2736	2773 T. D.

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1963

CONSERVATION DIVISION
Wichita, Kansas