

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-20898-00-00

LEASE NAME T.J. Isom

RECEIVED

SEP 10 2002

Westport Oil & Gas  
Southern Division

LEASE OPERATOR Westport Oil & Gas Company L.P.

ADDRESS P.O. BOX 864 / JOHNSON CITY, KANSAS 67855

PHONE#(316) 492-1435 OPERATORS LICENSE NO. 8733

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on DODGE CITY, KANSAS (8-27-02) (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHESTER Depth to Top 6121 Bottom 6144 T.D. 6415

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chester	Oil & Gas	6121	6144	8 5/8	1782	-0-
				5 1/2	6415	-2023-
				2 7/8	6135	5960

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Cut off tubing @5960' circulated hole with 120 bbl mud. Set CIBP @5950' with 2 sx. cement on top. Cut casing off @2023' pump 50 sx. cement from 1810 to 1650. Pump 40 sx. cement 550 to 450'. Pump 10 sx. cement from 40 to surface. Cut off & weld steel I.D. plate 4' B.G.L.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jerry Dunkin Well Services, Inc. License No. 8733

Address P O Box 389, Enid, OK 73702

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Dunkin

(Address) 8908 S Yale, Ste 340, Tulsa, OK

RECEIVED

SEP 12 2002 9-12-02


KCC WICHITA

SUBSCRIBED AND SWORN TO before me this 11th day of Sept 2002

Walter Blackwell  
Notary Public  
My Commission Expires May 21, 2005

My Commission Expires: \_\_\_\_\_

#01008557



OR