

R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20393-00-00
Spot: SENWNW Sec/Twnshp/Rge: 20-32S-36W
1250 feet from N Section Line, 1250 feet from W Section Line
Lease/Unit Name: KENOYER - 2 UNIT Well Number: 3
County: STEVENS Total Vertical Depth: 3085 feet

Operator License No.: 5208
Op Name: MOBIL OIL CORPORATION
Address: PO BOX 4358
HOUSTON, TX 77210

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 604 WITH 350 SX CMT
Production: Size 5.5 feet: 3085 WITH 350 SX CMT
Liner: Size _____ feet: \$100.26

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/22/2001 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: 1ST PLUG AT 1000' WITH 40 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 05/22/2001 1:45 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 3053'. PERFS AT 2944-2980'. TUBING FISH @ 1401'. PULLED 1011' OF CASING OUT OF HOLE. RAN 2 3/8" TUBING TO 1360' STACKED OUT. 1ST PLUG PULLED UP TO 1335' LOADED HOLE WITH MUD. CIRCULATED MUD TO SURFACE. PUMPED 25 SX CMT AT 1335'. 2ND PLUG PULLED UP TO 1000' PUMPED 40 SX CMT. 3RD PLUG PULLED UP TO 630' PUMPED 50 SX CMT. 4TH PLUG PULLED UP TO 40' PUMPED 10 SX CMT.

INVOICED
DATE 5-31-01
INV. NO. 2001061872
RECEIVED
KANSAS CORPORATION COMMISSION
5-31-01
MAY 31 2001
CONSERVATION DIVISION

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1011' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed Kevin P. Strube
(TECHNICIAN)

MAY 30 2001

Form CP-2/3

MP