

2332

To: 1 020020  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 189-20,908-0000  
SW SE SE, SEC. 3, T 32 S, R 36  
470 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5208  
Operator: Mobil Oil Corporation  
Name & Address: P. O. Box 5444  
Denver, CO 80217

Lease Name L.L. Barngrover Well # 1  
County Stevens 212.88  
Well Total Depth 6550 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1834

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mobil Oil Corporation License Number 5208

Address P. O. Box 5444, Denver, CO 80217

Company to plug at: Hour: 10:00 am Day: 16 Month: June Year: 19 86

Plugging proposal received from N/A

(company name) Mobil (phone) 303-298-2047

were: DV at 3235-2360' Perfs at 5897-5934' CIBP at 5850 and 2" sx cement

Fill 5 1/2" at point of DV job.- 100' plug at 1850-1750 inside and out of 5 1/2"

100' plug at 900' inside and out and from 40' to surface inside and out.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 pm Day: 16 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5850' with 2 sx cement, 2nd plug load hole with mud and spot 30 sx at 3235', 3rd plug perforate from 1878-1880 and pump 125 sx cement with good returns on backside, 4th plug spotted 20 sx cement at 900', 5th plug spotted from 40' to surface with 10 sx cement.

Remarks: Used Class H with 6% gel by Halliburton. No recovery.  
(If additional description is necessary, use BACK of this form.)

DATE JUL 10 1986  
INV. NO. 14324  
JUL 8 1986  
JUL 24 1986  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: *Richard W. Lacey*  
(TECHNICIAN)

