

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20784-00-00
Spot: CSENE Sec/Twnshp/Rge: 11-32S-35W
660 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: H H WULFMEYER Well Number: 1
County: STEVENS Total Vertical Depth: 6450 feet

Operator License No.: 31269
Op Name: BELCO ENERGY CORP.
Address: 5735 PINELAND STE 300
DALLAS, TX 75231

Conductor Pipe: Size _____ feet:
Surface Casing: Size 9.625 feet: 1875 WITH 600 SX CMT
Production: Size 5.5 feet: 6448 WITH 675 SX CMT
Liner: Size _____ feet: \$209.63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/02/2001 9:30 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: TYLER Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 6020' & 2 SX CMT. 1ST PLUG AT 1900' WITH 75 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/02/2001 12:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6405'. PERFS AT 6070-6076'. TOC 2430'. DV TOL @ 3130'. SET CIBP @ 6020' WITH 2 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG AT 1914' WITH 75 SX CMT. LOAD HOLE WITH MUD. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 11 2001
CONSERVATION DIVISION

INVOICED
DATE 7-11-01
INV. NO. 2002060041

Remarks: USED COMMON CEMENT BY ALLIED. RECOVERED 2010' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland PART II
(TECHNICIAN)

JUL 06 2001

Form CP-2/3

MP