

1030886

11-12-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-20,322-00-00
140' S of
C. NW NE, SEC. 13, T. 32 S, R. 35 W/E
4480 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4951

Lease Name Larrabee Well # 5

Operator: Claxson Exploration Company

County Stevens 200.85

Name & Address 427 South Boston, Suite 1901

Well Total Depth 6180 feet

Tulsa, OK 74103

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1719

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 10 a.m. Day: 8 Month: 11 Year: 19 87

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 6169' PBTD 6126' Perfs at 6105-14' Elevation 2974' GL

1st plug pump 2 sx hulls and 25 sx cement on bottom,

2nd plug at free point with 25 sx cement,

3rd plug at Bt Sp with 50 sx cement, 4th plug at 650' with 25 sx cement,

5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5 p.m. Day: 12 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to 5800',

2nd plug pumped 25 sx cement at 2700-2600',

3rd plug pumped 50 sx cement at 1750-1650',

4th plug pumped 25 sx cement at 650-575',

5th plug pumped 10 sx cement at 40-0'.

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Midwest. Recovered 2750' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

did not observe this plugging.

DATE NOV 20 1987

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 18901