

1 030432

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-20,842-00-00

C NW SE, SEC. 21, T 32 S, R 35 W/K
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name Fern Sessler Well # 1

Operator: Mobil Oil Corporation
Name & Address: P. O. Box 5444
Denver, CO 80217

County Stevens 213.43 (Lansing)
Well Total Depth 6567 feet
Conductor Pipe: Size 20" feet 70'
Surface Casing: Size 8 5/8 feet 1797

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x _____

Other well as hereinafter indicated _____

Plugging Contractor Unit Drilling & Exploration Co. License Number 9137
Address Box 702500, Tulsa, OK 74170

Company to plug at: Hour: 9:00 pm Day: 6 Month: June Year: 19 85

Plugging proposal received from Richard Bailey
(company name) Mobil (phone) 303-298-2047

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1850

1st plug at 3254' with 75 sx cement

2nd plug at 2694' with 60 sx cement

3rd plug at 1850' with 75 sx cement

4th plug at 800' with 50 sx cement
solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Steve Durrant
cement to surface with 10 sx cement (TECHNICIAN)

7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse hole with
Plugging Operations attended by Agent: All _____ Part x _____ None _____
10 sx cement

Operations Completed: Hour: 12:00 pm Day: 7 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3254' with 75 sx cement, 2nd plug at 2694' with 60
sx cement, 3rd plug at 1850' with 75 sx cement, 4th plug at 800' with 50 sx cement, 5th
& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement
7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse hole with
10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1985

Remarks: Used Class H Cement 3% cc & Redi-Mix Cement by Halliburton
(If additional description is necessary, use BACK of this form)
James R. Kapp observed part of the plugging CONSERVATION DIVISION
Wichita, Kansas
if (did / ~~xxxxxxx~~) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

INVOICED

DATE 6-20-85
8641

INV. NO. 6-7 JUL 12 1985

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL ^{yes}
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: February 2, 1985
month day year

API Number 15- 189-20,842-0000

OPERATOR: License # 5208

C NW SE Sec 21 Twp 32 S, Rge 35 East West

Name Mobil Oil Corporation

Address P.O. Box 5444

City/State/Zip Denver, Colorado 80217

Contact Person J. L. Douglass

Phone (303) 298-2047

CONTRACTOR: License # ~~Contractor not selected~~ advise on

Name ~~AGC 1 or sooner if required~~

City/State ~~AGC 1 or sooner if required~~

Well Drilled For: Well Class: Type Equipment:

Oil Swd Infield Mud Rotary

Gas Inj Pool Ext. Air Rotary

OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator Unit Drilling & Exploration Co.

Well Name Box 702500

Comp Date July, OK Old Total Depth 74170

Projected Total Depth 6550 feet

Projected Formation at TD St. Louis

Expected Producing Formations Chester

Verify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Surface pipe will be set at least 25' into White Horse Sandstone.

to 1/16/85 Signature of Operator or Agent J. L. Douglass

1980 Ft North from Southeast Corner of Section

1980 Ft West from Southeast Corner of Section

(Note: Locate well on Section Plat on reverse slide)

Nearest lease or unit boundary line 1980 feet.

County Stevens

Lease Name Fern Sessler Well# 1

Domestic well within 330 feet: yes no

Municipal well within one mile: yes no

Depth to Bottom of fresh water 575 feet

Lowest usable water formation Permian

Depth to Bottom of usable water 600 feet

Surface pipe by Alternate: 1 2

* Surface pipe to be set 625 feet

Conductor pipe if any required None feet

Ground surface elevation 3008 feet MSL

This Authorization Expires 7-22-85

Approved By 1-22-85

WW Regulatory Compliance Mgr.

Form C-1 4/84

now in 5-24-85 set - 1850' 95' mhc / KOHE 1-22-85

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1985

CONSERVATION DIVISION
Wichita, Kansas