

1 061034

11-4-87

API NUMBER 15-189-20,321-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
260 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NE NE, SEC. 24, T 32 S, R 35 W/E

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4951

Lease Name Arco-Davis Well # 2

Operator: Claassen Exploration Company  
Name

County Stevens 201.50

Address 427 South Boston, Suite 1901

Well Total Depth 6200 feet

Tulsa, OK 74103

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1715

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 10 a.m. Day: 4 Month: 11 Year: 19 87

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 6200' PBD 6167' Perfs at 6024-6122' Elevation 2969' GL

1st plug pump 2 sx hulls and 25 sx cement, 2nd plug at 2680' with 25 sx cement,

3rd plug at 1750' with 50 sx cement, 4th plug at 650' with 25 sx cement,

5th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5 p.m. Day: 4 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement,

2nd plug pumped 25 sx cement at 2680',

3rd plug pumped 50 sx cement at 1750',

4th plug pumped 25 sx cement at 650',

5th plug pumped 10 sx cement at 40-0'.

Remarks: Used common cement by Midwest Casing Pulling. Recovered 2722' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-12-87

INV. NO. 18828

NOV 6 1987  
11-6-87  
Signed  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Paul A. Luthi  
(TECHNICIAN)