

To: 100005
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-189-20,527-00-01
C SE NW, SEC. 24, T 32 S, R 35 W/XX

TECHNICIAN'S PLUGGING REPORT

12-21

Operator License # 30606
Operator: Murfin Drilling Company, Inc.
Name & Address: 250 N. Water, Ste. 300
Wichita, KS 67202

3300 feet from S section line
3300 feet from E section line
Lease Name Moore (Trex) Well # 1
County Stevens
Well Total Depth 6197 201.40 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1707

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529
Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 21 Month: 12 Year: 19 95

Plugging proposal received from Manny Boatright
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Remarks: 4 1/2" at 6194' w/450 sx cement, PBSD 6153', Perfs at 6092-6112'

- 1st plug sand back to 6050' and dump 4 sx cement on top of sand through bailer,
- 2nd plug at 1740' with 50 sx cement, 3rd plug at 1100' with 50 sx cement,
- 4th plug at 500' with 25 sx cement,
- 5th plug at 40-0' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

12-27-95 DEC 27 1995

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Durran (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:15 p.m. Day: 21 Month: 12 Year: 19 95

- ACTUAL PLUGGING REPORT 1st plug sanded back to 6050' and dumped 4 sx cement on top of sand through bailer,
- 2nd plug at 1740' with 50 sx cement,
 - 3rd plug at 1111' with 50 sx cement,
 - 4th plug at 550' with 25 sx cement,
 - 5th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1751' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy of original) observe this plugging.

DATE JAN 09 1996
INV. NO. 4445-3

Signed Gary Winters (TECHNICIAN)