

7-12-88

1 020163

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-20,806-0000
C NE NW, SEC. 24, T 32 S, R 35 W/EX
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5941
Operator: Rosel Energy, Inc.
Name & Address Box 1068
Liberal, KS 67905-1068.

Lease Name Pittman Well # 1
County Stevens 202.54
Well Total Depth 6232 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1715

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 4 p.m. Day: 7 Month: 7 Year: 19 88

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 6232' PBD 6190' Perfs at 6090-96'
1st plug pump 100 lbs hulls and 25 sx Portland cement,
2nd plug pump 50 sx cement at 2850', 3rd plug pump 50 sx cement at 1740',
4th plug pump 35 sx cement at 850', 5th plug pump 10 sx cement at 40'-5'.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 3 p.m. Day: 12 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to bottom,
2nd plug pumped 50 sx cement at 2850',
3rd plug pumped 50 sx cement at 1740',
4th plug pumped 35 sx cement at 850',
5th plug pumped 10 sx cement at 40-5'.

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3200' of 5 1/2" casing.
Additional description is necessary, use BACK of this form.)

DATE 7-26-88

INV. NO. 21676

7-12

Signed [Signature]
(TECHNICIAN)