

7-11

1 120451

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-21,351 - 0000

C NE NE, SEC. 28, T 32 S, R 35 W4E

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name Mueller Trust Well # 1-28

Operator: McCoy Petroleum Corporation

County Stevens 209.33

Name & Address 110 S. Main, Suite 500

Well Total Depth 6441 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1729

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hayes Well Service License Number 5429

Address Attica, KS

Company to plug at: Hour: 1:30 p.m. Day: 11 Month: 7 Year: 19 90

Plugging proposal received from Daryl Hanson

(company name) McCoy Petroleum Corporation (phone) 316-256-3510

were: 5 1/2" at 3164' cemented w/275 sx. PBTD 3101'. Perfs at 3003-16', reperforated at 3007.5-3015.5'
TOC 1350'

1st plug pump 50 sx cement at 1340',

2nd plug pump 40' cement at 702',

3rd plug pump 10 sx cement at 40'.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 p.m. Day: 11 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement at 1340',

2nd plug pumped 40 sx cement at 702',

3rd plug pumped 10 sx cement at 40'.

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 1350' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (XXXXXX) observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 7-24-90

INV. NO. 28219