

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20941-00-00
Spot: CSW Sec/Twnshp/Rge: 34-32S-35W
1320 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: DOWNING - UNIT 1 Well Number: 2
County: STEVENS Total Vertical Depth: 6398 feet

Operator License No.: 5208
Operator Name: MOBIL OIL CORPORATION
Address: PO BOX 4358
HOUSTON, TX 77210

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 1776
Production: Size 5.5 feet: 6398 207.94
Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/09/2000 11:00:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: 1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 10/10/2000 10:00 AM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 5954-5960'. CIBP @ 5900' WITH 2 SX CMT. SPOTTED PLUGS THROUGH CASING. HEAVY MUD BETWEEN PLUGS. 1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 2000

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2241' OF 5 1/2" CASING.

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 11/1/00

INV. NO. 2001060911

OCT 26 2000

OP-2/3

MP