

1050836

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION -  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-189-20,917-0000

SE NE SE, SEC. 35, T 32 S, R 35 W/EX

1650 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name Josephine S. Burchett Well # 2

Operator: Mobil Oil Corporation

County Stevens 208.00

Name & Address P.O. Box 5444

Well Total Depth 6400 feet

Denver, CO 80217

Conductor Pipe: Size            feet

Surface Casing: Size 8 5/8 feet 1802

Abandoned Oil Well            Gas Well            Input Well            SWD Well            D&A X

Other well as hereinafter indicated           

Plugging Contractor Unit Drlg. & Expl. Co. License Number 9137

Address 1000 Galleria Twr 1, 7130 S. Lewis, P.O. Box 702500, Tulsa, OK 74136

Company to plug at: Hour: 9:00 am Day: 25 Month: July Year: 1986

Plugging proposal received from Jeff Nelson

(company name) Mobil (phone) (303) 298-2047

were: to fill the hole with heavy mud and spot cement through drill pipe Anhydrite 1800'

1st plug at the Chester with 40 sx cement

2nd plug at 3200' with 40 sx cement

3rd plug at 2900' with 40 sx cement

4th plug at 2600' with 40 sx cement

5th plug 75' below surface casing with 75 sx cement

6th plug 600' with 50 sx cement

7th plug 40' to surface with 14 sx cement.

8th plug to circulate rat hole with 20 sx cement

9th plug to circulate mouse hole with 20 sx cement

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part            None           

Operations Completed: Hour: 2:30 pm Day: 25 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 5898' with 60 sx cement, 2nd plug at 3368' with 70

sx cement, 3rd plug at 3025' with 70 sx cement, 4th plug at 2595' with 70 sx

cement, 5th plug at 1887' with 80 sx cement, 6th plug at 620' with 50 sx cement,

7th plug from 40' to surface with 15 sx cement, 8th plug to circulate rat hole

with 20 sx cement, 9th plug to circulate mouse hole with 20 sx cement

Remarks: Used Class H cement with 3% calcium dichloride.

(If additional description is necessary, use BACK of this form.)

(If additional observations observe this plugging.)

DATE JUL 31 1986

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 14589 7-2-F AUG 29 1986

RECEIVED  
STATE CORPORATION COMMISSION  
CONSV. DIV. WICHITA, KS  
7-31-86  
JUL 31 1986