

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20898-00-00
Spot: W2NENW Sec/Twnshp/Rge: 35-32S-35W
4620 feet from S Section Line, 3500 feet from E Section Line
Lease/Unit Name: T J ISOM Well Number: 2
County: STEVENS Total Vertical Depth: 6415 feet

Operator License No.: 33002 Conductor Pipe: Size feet: 208.49
Op Name: WESTPORT OIL AND GAS COMPANY LP Surface Casing: Size 8.625 feet: 1782 WITH 985 SX CMT
Address: 5735 PINELAND, SUITE 300 Production: Size 5.5 feet: 6415 WITH 442 SX CMT
DALLAS, TX 75231 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/05/2001 10:00 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: BUTCH DUNKIN Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 5950'. 1ST PLUG AT 1810' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/05/2002 12:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:
PBT 6215'. PERFS AT 6121-44'. SET CIBP @ 5950' WITH 2 SX CMT. TOP OF FISH AT 5960'. 1ST PLUG PULL OUT OF HOLE WITH 5 1/2" TO 1810'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH 39 BBL MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 550'. LOAD HOLE & PUMP 40 SX CMT. DISPLACE WITH 11 BBL MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 10 SX CMT TO SURFACE.

RECEIVED
SEP 19 2002 9-19-02
KCC WICHITA

Remarks: USED CLASS A CMT BY JERRY DUNKIN, INC. RECOVERED 2023' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland PIRTH
(TECHNICIAN)

INVOICED SEP 16 2002
DATE 9-19-02
INV. NO. 2003060535

