

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20918-00-00  
Spot: NWSESENW Sec/Twnshp/Rge: 35-32S-35W  
3300 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: T J ISOM Well Number: 3  
County: STEVENS Total Vertical Depth: 6401 feet

Operator License No.: 33002 Conductor Pipe: Size feet: 8208.03  
Op Name: WESTPORT OIL AND GAS COMPANY LP Surface Casing: Size 8.625 feet: 1770 WITH 720 SX CMT  
Address: 5735 PINELAND, SUITE 300 Production: Size 5.5 feet: 6401 WITH 360 SX CMT  
DALLAS, TX 75231 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/02/2002 9:00 AM  
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.  
Proposal Rcvd. from: BUTCH DUNKIN Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 6075' WITH 2 SX CMT. PLUG AT 1800' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/02/2002 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6155'. PERFS AT 6123-6142'. SET CIBP @ 6075' WITH 2 SX CMT ON TOP. PULL OUT OF HOLE TO 1850'. 1ST PLUG CIRCULATE HOLE WITH MUD. PUMP 60 SX CMT AT 1817'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 534'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH 5 1/2" TO 40' & PUMP 15 SX CMT TO SURFACE.

RECEIVED  
OCT 17 2002  
KCC WICHITA

Remarks: USED COMMON CEMENT BY JERRY DUNKIN, INC. RECVOERED 2012' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland FIRTH  
(TECHNICIAN)

INVOICED  
DATE 10-18-02 OCT 09 2002  
INV. NO. 2003060660 MP

Form SP 2/3