

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21143-00-00
Spot: N2NE Sec/Twnshp/Rge: 1-32S-35W
4620 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: KU ENDOWMENT Well Number: 3
County: STEVENS Total Vertical Depth: 6210 feet

Operator License No.: 31269
Operator Name: BELCO ENERGY CORP.
Address: 5735 PINELAND STE 300
DALLAS, TX 75231

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 1803 WITH 760 SX CMT
Production: Size 5.5 feet: 6210 WITH 670 SX CMT
Liner: Size _____ feet: 2016 83

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2000 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: BOTTOM PLUG PUMP 300# HULLS & 15 SX GEL. PUMP 50 SX CMT AT 1800'. PULL TO 690' AND PUMP 50 SX CMT. PUMP 10 SX CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 11/21/2000 3:45 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: HILTON HIXON

Actual Plugging Report:

PERFS AT 6037-6044 & 6059-6082. BOTTOM PLUG PUMP 300# HULLS & 15 SX GEL. 1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG PULL UP TO 690' & PUMP 50 SX CMT. 3RD PLUG PULL UP TO 40' & PUMP 10 SX CMT TO SURFACE.

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 2000

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1923' OF 5 1/2" CASING.

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: CSG

District: 01

Signed _____

Hilton Hixon

(TECHNICIAN)

INVOICED

DATE

11/28/00

NOV 27 2000

INV. NO.

2001061023

[Signature]
Form CP-2/3