

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21142-00-00
Spot: SWNE Sec/Twnshp/Rge: 1-32S-35W
3300 feet from S Section Line, 1880 feet from E Section Line
Lease/Unit Name: K.U. ENDOWMENT Well Number: 2
County: STEVENS Total Vertical Depth: 6310 feet

Operator License No.: 31269
Operator Name: BELCO ENERGY CORP.
Address: 5735 PINELAND STE 300
DALLAS, TX 75231

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 1762 WITH 759 SX CMT
Production: Size 5.5 feet: 6310 WITH 720 SX CMT
Liner: Size _____ feet: 205.08

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2000 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 3 SX HULLS & 25 SX CMT FOR BOTTOM PLUG. 1ST PLUG AT 1770' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/16/2000 2:30 PM KCC Agent: HILTON HIXON

Actual Plugging Report:

PERFS AT 6037-6056, 6068-6080, 6086-6100'. ESTIMATED TOP OF CMT 2415'. PUMP 300# HULLS WITH 25 SX CMT. PRESSURED UP TO 500#. 1ST PLUG PULLED CASING UP TO 1770' & PUMP 50 SX CMT. DISPLACED WITH 41 BBL MUD. 2ND PLUG PULL CASING UP TO 690' & PUMP 40 SX CMT. DISPLACED WITH 14 BBL MUD. 3RD PLUG PULL UP TO 40' & PUMP 10 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION
NOV 28 2000

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2230' OF 5 1/2" CASING.
Plugged through: CSG

District: 01

Signed Hilton Hixon
(TECHNICIAN)

INVOICED
DATE 11/28/00
INV. NO. 2001061023

NOV 20 2000

Form 623

MP