

1 020253

9-8

24 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-21,347-0000
C NW SW, SEC. 2, T 32 S, R 35 W/E
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name Wulfemeyer "A" Well # 1-2

Operator: McCoy Petroleum Corporation
Name & Address 110 South Main, Suite 500
Wichita, KS 67202

County Stevens 206.38

Well Total Depth 6350 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1758

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor McCoy Petroleum Corporation License Number 5003

Address 110 South Main, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 3:30 p.m. Day: 8 Month: 9 Year: 19 89

Plugging proposal received from Daryl Hanson

(company name) McCoy Petroleum Corporation (phone) 316-532-5292

were: 4 1/2" at 6344' PBDT 6344' Perfs at 6077-87 F.O. Tool at 3302'

1st plug set CIBP at 6000' with 4 sx cement, 2nd plug pump 50 sx cement at 3150',

3rd plug pump 50 sx cement at 2600', 4th plug pump 40 sx cement at 1780',

5th plug pump 40 sx cement at 600',

6th plug pump 10 sx cement at 40'.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 6 p.m. Day: 8 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5980' with 3 sx cement on top,

2nd plug cut casing at 5980', 2nd cut at 3349', pumped 100 sx cement at 3050',

3rd plug pumped 40 sx cement at 1790',

4th plug pumped 40 sx cement at 700',

5th plug pumped 20 sx cement at 60-0'.

RECEIVED
STATE CORPORATION COMMISSION
SEP 12 1989
CONSERVATION DIVISION

Remarks: Recovered 3349' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 9-18-89

Signed John R. Barber
(TECHNICIAN)

INV. NO. 25905