

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21092-00-00
Spot: CSESE Sec/Twnshp/Rge: 2-32S-35W
660 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: GERTRUDE LOGAN Well Number: 1
County: STEVENS Total Vertical Depth: 6327 feet

Operator License No.: 33002
Op Name: WESTPORT OIL AND GAS COMPANY L
Address: 5735 PINELAND, SUITE 300
DALLAS, TX 75231

Production Casing Size: 5.5 feet: 6327 WITH 1100 SX CMT
Surface Casing Size: 8.625 feet: 1786 WITH 830 SX CMT

205.63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2003 10:00 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: BUTCH DUNKIN Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 4700' WITH 2 SX CMT. RUN TUBING TO 1800' & PUMP 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/10/2003 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ 4700'. PERFS AT 6088-6126, 4756-64, 4806-10'. CIBP'S @ 5160-5930'. DV TOOL AT 3237' ESTIMATED TOC @ 2290'. SET CIBP @ 4700' WITH 2 SX CMT. LOAD HOLE WITH MUD. SHOOT OFF CASING AT 2005' & PULL OUT OF HOLE WITH CASING. 1ST PLUG RUN IN HOLE WITH 2 7/8" TUBING TO 1800'. LOAD HOLE & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 550' & PUMP 40 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH TUBING TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

RECEIVED
MAR 24 2003
KCC WICHITA

Remarks: USED CLASS A W/1% CC BY DUNKIN WELL SERVICE. RECOVERED 2005' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

RECEIVED
MAR 20 2003
KCC Dodge City

Signed Jim Holland (TECHNICIAN)

INVOICED
DATE 3-25-03
INV. NO. 2003061327

Form C-113