

1110097

2-4-88 15-189-00082-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 5/45

Center, SEC. 6, T 32 S, R 35 W/E

2640 feet from S section line

2640 feet from E section line  
#1 Unit

Lease Name Brownell Well # 1

County Stevens 91.94

Well Total Depth 2829 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 600

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Operator: Mobil Oil Corporation

Name & Address P.O. Box 5444

Denver, CO 80217

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mobil Oil Corporation License Number 5208

Address P.O. Box 5444, Denver, CO 80217

Company to plug at: Hour: 9 a.m. Day: 1 Month: 2 Year: 19 88

Plugging proposal received from Tom Romero

(company name) Mobil Oil Corporation (phone) 316-544-4316

were: 4 1/2" at 2651', 7" at 2662'

1st plug pump 25 sx cement to bottom,

2nd plug perforate at 950' and run tubing to 1830' and pump 70 sx cement,

3rd plug perforate at 655' and pump 100 sx cement.

Plugging Proposal Received by James R. Kapp  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 10:40 a.m. Day: 4 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement and wooden plug followed by wire line  
which stopped at 2601,

2nd plug shot 4 1/2" at 950', ran tubing to 1830' and pumped 70 sx cement, RECEIVED

3rd plug perforated 7" at 655' and pumped 100 sx cement, STATE CORPORATION COMMISSION

4th plug perforated 7" at 425' and pumped 191 sx cement. 2-10-88 FEB 10 1988

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 50/50 Pozmix 3% cc by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I ( ) did not observe this plugging.

Signed James R. Kapp  
(TECHNICIAN)

DATE 2-12-88

INV. NO. 19832 2-4 MAR 24 1988