

1 020340

11-29

API NUMBER 15-189-21,262-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NW NW, SEC. 10, T 32 S, R 35 W&E

4414 feet from S section line

4018 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name Vernon Combes Well # 3

Operator: Mobil Oil Corporation

County Stevens 205.40

Name & Address 2319 N. Kansas

Well Total Depth 6320 feet

Liberal, KS 67901

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1772

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mobil Oil Corporation License Number 5208

Address 2319 N. Kansas, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 29 Month: 11 Year: 19 90

Plugging proposal received from Tommy Romero

(company name) Mobil Oil Corporation (phone) 316-544-4326

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3218' with 40 sx cement, 2nd plug at 3000' with 40 sx cement,

3rd plug at 2658' with 40 sx cement, 4th plug at 1843' with 60 sx cement,

5th plug at 750' with 30 sx cement, 6th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 29 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 10/9/88 1st plug at 3218' with 40 sx cement,

2nd plug at 3000' with 40 sx cement,

3rd plug at 2658' with 40 sx cement,

4th plug at 1843' with 60 sx cement. All Class H cement. T/Ad 11/21/88.

11/29/90 5th plug tagged cement at 1700' circulated with jel mud, spotted 30 sx cement

at 700'. 6th plug spotted 20 sx cement at 60-0'. DEC 4 1990 12-4-90

Remarks: Used 50/50 Pozmix by Halliburton.

CONSERVATION DIVISION

(if additional description is necessary, use BACK of THIS form.)

INVOICED (if applicable) observe this plugging.

Signed Steve R. Barlow (TECHNICIAN)

DATE 12-7-90

INV. NO. 30192

~~AMENDED AS TO LOCATION~~

NOTICE OF INTENTION TO DRILL

(see 1 1/2 on reverse side)

Starting Date 9/23/88  
month day year

API Number 15-189-21,262

OPERATOR: License # 5208

\* SE NW NW Sec. 10 Twp. 32 S. R. 17  
\* 4413.8 Ft. from  
\* 4018.05 Ft. from

Name Mobil Oil Corporation

Address P. O. Box 5444

City/State/Zip Denver, CO 80217

Contact Person B. R. Maynard

Phone (303) 298-2069

CONTRACTOR: License # Contractor not selected.

Name Will advise on ACO-1

City/State

Well Drilled For: Well Class: Type Equipment:

Oil  SWD  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

(Note: Locate well on Section Plat on rev. \*848

Nearest lease or unit boundary line

County Stevens

Lease Name Vernon Combes We

Ground surface elevation \*2997.4

Domestic well within 330 feet:

Municipal well within one mile:

Depth to bottom of fresh water 575

Depth to bottom of usable water 600

Surface pipe by Alternate:

Surface pipe planned to be set 625

Conductor pipe required None

Projected Total Depth 6400

Formation St. Louis, Chester

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 9/9/88 Signature of Operator or Agent B. R. Maynard Title Regulatory Co.

For KCC Use:

Conductor Pipe Required \_\_\_\_\_ feet; Minimum Surface Pipe Required 620'

This Authorization Expires 2-26-89 Approved By LKM 9-12-88 ORIG. REC'D

EFFECTIVE DATE: 2-31-88

\* WAS: E/2 W/2 NW, 3943.1' FSL, 4417.6  
820' NEAREST UNIT LINE, 2999.0

*NO CALL ON SPUD*

*Set 898 @ 1772*

*Spud 10-1-88*

*TA/120 DAY for well sand later to confirm*

PUSHER	FORMATION																			
TD																				
SURFACE PIPE @		ELEVATION																		
ANHYDRITE																				
STARTING TIME & DATE																				
COMPLETION TIME & DATE																				
1st PLUG @		FT. W/																		
2nd PLUG @		FT. W/																		
3rd PLUG @		FT. W/																		
4th PLUG @		FT. W/																		
RAE HOLE CIRCULATED W/																				
MOUSE HOLE CIRCULATED W/																				
WATER WELL PLUGGED W/																				
COMPANY																				
TECHNICIAN																				

*plugged bottom gave 10-8 to d. ket Ray Co Ray @. it*

RECEIVED STATE CORPORATION COMMISSION DEC 4 1988

CONSERVATION DIVISION Wichita, Kansas