

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-21124-00-00  
Spot: SENWSENE Sec/Twnshp/Rge: 10-32S-35W  
3330 feet from N Section Line, 690 feet from W Section Line  
Lease/Unit Name: COMBS GENEVIEVE Well Number: 1  
County: STEVENS Total Vertical Depth: 6300 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: PO BOX 4358  
HOUSTON, TX 77210

Production Casing Size: 5.5 feet: 6287 WITH 460 SX CMT  
Surface Casing Size: 8.625 feet: 1842 WITH 950 SX CMT

\$204.75

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/11/2003 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 6000' WITH 2 SX CMT. PLUG AT 1870' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/14/2003 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 6203'. PERFS AT 6085-6107'. TOC @ 5330'. DV TOOL @ 3295' WITH 260 SX CMT. CIBP @ 6000' WITH 2 SX CMT. 1ST PLUG PULL OUT OF HOLE TO 1870'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 550'. SDON. 04/14/03: LOAD HOLE & PUMP 40 SX CMT. DISPLACE WITH MUD. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED  
APR 29 2003  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2335' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PERTH  
(TECHNICIAN)

INVOICED  
DATE 4-29-03  
INV. NO. 2003061471

FORM 2/98