

1052404
TO: STATE CORPORATION COMMISSION

API NUMBER 15-189-22,339-0000
50' W SE SW NE SEC. 27, T 32 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1700 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SCHMIDT "D" WELL # 1
COUNTY STEVENS 204.82

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 4549 WELL TOTAL DEPTH 6302 FEET

OPERATOR: ANADARKO PETROLEUM CORPORATION PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8" @ 1632 ' WITH SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR BIG A DRILLING LICENSE NUMBER 31572

ADDRESS PO BOX 1856 LIBERAL, KS 67901

COMPANY TO PLUG AT: HOUR: 11:00 PM DAY: 16 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM JIM BARLOW

(COMPANY NAME) BIG A DRILLING (PHONE) 316-624-1904

WERE:

1ST PLUG AT 3200' WITH 100 SX CEMENT. 2ND PLUG AT 1660' WITH 50 SX CEMENT.

3RD PLUG AT 600' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 2:15 AM DAY: 17 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 3200' WITH 100 SX CEMENT. 2ND PLUG AT 1660' WITH 50 SX CEMENT.

3RD PLUG AT 600' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY B J SERVICES.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID NOT) OBSERVE THIS PLUGGING.

INVOICED
7/5/00
SIGNED Richard W. Lacey
(TECHNICIAN)
FORM CP-2/3
WV. NO. 1060007
RECEIVED STATE CORPORATION COMMISSION JUL 03 2000 CONSERVATION DIVISION Wichita, Kansas

