


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Sumner County, Sec. 16 Twp. 35 Rge. 3 (E) (W)

Location as "NE/CNW/SW" or footage from lines Lot 3, Sec. 16
Lease Owner Ben F. Brack Oil Company, Inc.
Lease Name Dora I. Williams Well No. 1
Office Address 309-10 Brown Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil & Gas
Date well completed 6-30-52 19
Application for plugging filed 12-17-52 19
Application for plugging approved 12-17-52 19
Plugging commenced 12-17-52 19
Plugging completed 12-29-52 19
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 11-6-52 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington
Producing formation Mississippi Depth to top 4343 Bottom 4688 Total Depth of Well 4755 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface soil, shale & shells		0	360	8 5/8"	360'	None
Shale & Limestone	Oil, Gas, Water	4343	4750	5 1/2"	4749	3700

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4350 feet to 360 feet for each plug set.

Lanewell plug set @ 4350', mud to 2765', 2 sax cement on rock bridge, mud to 360', 15 sax cemented on 10' rock bridge, mud to 20', 10 sax cement from 20' to surface.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Charles Oakes Casing Service
Address 2841 East Pawnee Road, Wichita, 16, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leland E. Brack (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leland E. Brack
309-10 Brown Bldg., Wichita 2, Kansas (Address)

Subscribed and sworn to before me this 31st day of December, 1952
Gertrude Crist
Notary Public.



1-8-53

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 - 1953
CONSERVATION DIVISION
Wichita, Kansas

BEN F. BRACK OIL COMPANY, INC.
 309-10 BROWN BUILDING
 WICHITA 2, KANSAS

Dora E. Williams #1

NW NW NW

Lot 3, Sec. 16-358-3W
 Sumner County, Kansas
 Commenced: 5-28-52
 Completed: 6-30-52

Total Depth: 4750'
 Elevation: 1132 DF
 1125 Gr.

WELL LOG

Sandy Shale - Shells	0-	100'
Shale - Shells		360
Shale		433
Red Bed - Shale		615
Lime & Shale		920
Shale & Shells		1100
Lime - Shale		1190
Lime		1345
Lime & Shale		1515
Shale - Lime		1900
Lime & Shale		2050
Shale & Lime		2360
Lime & Shale		2500
Shale & Lime		2625
Lime		2785
Lime & Shale		2865
Lime		2970
Shale & Lime		3281
Sand, Shale & Lime		3410
Lime		3470
Shale & Lime		3665
Shale		3671
Sand		3695
Lime & Shale		3715
Shale & Lime		3752
Shale		3810
Lime		3825
Shale & Lime		3883
Lime & Shale		3937
Lime		4018
Lime - Sandy		4069
Lime - Shale		4123
Shale & Lime		4174
Lime - Shale		4222
Shale - Lime		4255
Shale		4335
Lime, Shale & Chert		4350
Lime		4415
Cherty Lime		4420
Lime		4430
Cherty Lime		4435
Lime & Chert		4446
Lime		4561
Lime - Chert		4574
Lime		4643
Lime & Shale		4700
Shale		4737
Lime		4750 T.D.

FORMATIONS

Stalnaker	3231'
Layton	3670'
Kansas City	3780'
Cherokee	4095'
Mississippian	4343'
Kinderhook	4688'
Viola	4743'
Simpson	4755'

PLUGGING
 SEC 16 T. 35 R. 34
 BOOK PAGE 661-32

Above depths indicate bottom of formations.

CASING RECORD

8 5/8" 360'
 5 1/2" 4749'

RECEIVED
 COMMISSION

JAN 9 - 1953

CONSERVATION DIVISION
 Wichita, Kansas

WITNESSED: *[Signature]*
 July 1, 1952.

To the best of my knowledge, the above is a true and correct statement of the depths and formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By *[Signature]*