


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

WELL PLUGGING RECORD

Sumner County, Sec. 15 Twp. 35S Rge. (E) 3 (W)

Location as "NE/CNW/SW" or footage from lines C NW SE
Lease Owner Stonehenge Oil Company
Lease Name Harry M. Stucky Well No. 1
Office Address 711 Franklin Building, Tulsa, Oklahoma 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced August 1, 1968
Plugging completed August 1, 1968
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Howard Hess)

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4977 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	268'	8-5/8"	7/18/68	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 300 Feet;
Plug and 35 sax Cement thru the Drill Pipe;
Heavy Mud to 40 Feet; Plug bridged with
Kelly and 8 sax Cement to Base of Cellar.
2 sax in Rat Hole. Job completed at 2:30 A.M.
on August 1, 1968.

RECEIVED
STATE CORPORATION COMMISSION
AUG 6 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SageeDrilling Co. (By Halliburton Truck)
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 1968

My commission expires November 26, 1970.

Louise K. Whitted, Notary Public.

R

DRILLERS LOGHARRY M. STUCKY NO. 1

CASING RECORD:	OPERATOR: Stonehenge Oil Co.	DESCRIPTION:
8-5/8" @ 268'	CONTRACTOR: Sage Drilling Co.	Ap. C NW SE
w/175 sax Cement	COMMENCED: July 18, 1968	Sec. 15-35S-3W
TOTAL DEPTH:	COMPLETED: August 1, 1968	Sumner County, Kansas
4977'		ELEVATION: 1198KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock & Red Shale	0	270	
Shale, Shells & Lime	270	877	
Shale & Lime	877	1285	
Lime & Shale	1285	1810	
Shale & Lime	1810	2515	
Lime & Shale	2515	2900	
Lime	2900	3012	
Shale & Lime	3012	3180	
Lime & Sand	3180	3325	
Shale & Lime	3325	3430	
Sand & Shale	3430	3564	
Lime & Shale	3564	3772	
Shale	3772	3815	
Lime & Shale	3815	3891	
Lime	3891	4215	
Lime & Shale	4215	4510	
Shale, Lime & Mississippi Chert	4510	4530	
Lime & Chert	4530	4560	
Lime, Shale & Chert	4560	4682	
Lime	4682	4742	
Lime & Chert	4742	4795	
Shale, Lime & Chert	4795	4834	
Chert & Lime	4834	4867	
Lime & Shale	4867	4909	
Shale & Lime	4909	4935	
Lime & Simpson Sand	4935	4965	
Simpson Sand	4965	4977	D&A

RECEIVED
STATE CORPORATION COMMISSION
AUG 6 1968
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer

Subscribed and sworn to before me this 5th day of August, 1968.

Louise K. Whitted
Louise K. Whitted, Notary Public



My commission expires:
November 26, 1970.