

15-191-10236-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely -
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sumner County, Sec. 9 Twp. 35 Rge. 3 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines SW NE NE

Lease Owner Texaco, Inc.

Lease Name N.J. Peters #4 Fall Creek Unit Well No. 4

Office Address Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 11/21/70 19

Plugging completed 11/25/70 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Dewey 4818

Producing formation Depth to top Bottom Total Depth of Well 4814 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	600'	none
				7"	4813'	2659.65

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded to 4760' and set 6 sacks of cement.
Shot pipe at 2956', 2862', 2767', 2674', pulled 86 joints.
Bailed hole to 300', set 35 sacks of cement. Mudded to 25' and ran 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 - 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.

Address CHASE, KANSAS


STATE OF KANSAS, COUNTY OF RICE, ss.

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight

CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 2nd day of December, 19 70.



Margaret Melcher Notary Public.

My commission expires 2/15/71

LOG OF WELL

SHEET NO. 2

District Kansas Owner The Texas Company Farm No. J. Peters Well No. 4

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
Sand & Clay					<p>CASING RECORD: 10-3/4" casing set at 604' with 150 sacks cement.</p> <p>7" casing set at 4813' with 500 sacks cement (250 thru DV tool at 4162' & 250 sacks around shoe).</p> <p>TOPS: Stalnaker.....3130 Layton.....3598 Kansas City....3647 Base K. C.....3846 Marmaton.....3920 Cherokee.....4072 Mississippi....4344 Kinderhook....4692 Misener.....4744 Viola.....4751 Simpson.....4764 Simpson Sd....4802 Total Depth...4814</p> <p>ELEVATIONS: 1124-----DF 1126-----KB 1118-----GL</p>
Shale Shells & Salt	600				
Lime & Shale	785				
Shale & Salt Sandy	830				
Shale & Lime	1256				
Lime & Shale	1490				
Shale & Lime	1585				
Shale & Lime Shells	1950				
Lime & Shale	3103				
Shale & Lime	3175				
Shale & Sand	3278				
Sand & Shale	3375				
Shale & Lime	3428				
Lime & Shale	3476				
Shale	3517				
Shale & Lime	3545				
Lime & Shale	3606				
Sand & Lime	3662				
Lime	3868				
Lime & Shale	3915				
Lime	3949				
Lime & Shale	3979				
Shale & Lime	4005				
Lime & Shale	4047				
Shale & Lime	4123				
Lime & Shale	4157				
Shale	4249				
Lime & Shale	4272				
Shale	4348				
Chat	4379				
Chat & Lime	4412				
Lime	4569				
Lime & Shale	4582				
Lime	4601				
Lime & Shale	4616				
Lime & Chert	4637				
Lime	4658				
Cherty Lime & Shale	4671				
Lime	4684				
Lime & Shale	4704				
Shale	4730				
Shale & Lime	4758				
Lime	4765				
Sand	4814				
Total Depth	4814				
PBTD	4808				

Measurement from 10" flange to KB 8' 8"

Top of cement 2955'

Lost circ. @ 4612' for 6 hours. Regained w/ Halls

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 5 1970
 CONSERVATION DIVISION
 Wichita, Kansas