

15-191-10238-0001
R

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sumner County, Sec. 9 Twp. 35 Rge. 3 (W)

Location as "NE/CNW/SW" or footage from lines. NE SE NE

Lease Owner Texaco, Inc.

Lease Name Hudson #1 (Ball Creek Unit Tract #5) Well No. 1

Office Address Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 10/24/70 19

Plugging completed 10/27/70 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hess

Producing formation Depth to top Bottom Total Depth of Well 4801 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	605	none
				5 1/2"	4782	1929

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 4765', cleaned cellar, took head apart. Welded collar on 5 1/2" casing, set 5 sacks of cement, rigged up on 5 1/2". Shot pipe at 2500', 2300', 1930', pulled 62 joints. Bailed hole to 300', set 15' rock bridge and ran 30 sacks mud to 25' and 5 sacks cement. Talled pipe.

PLUGGING COMPLETE.


RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)



SUBSCRIBED AND SWORN to before me this 5th day of November, 1970

Margaret Melcher
Notary Public.

My commission expires 2/15/71

15-191-10238-0001

DR

Record of Well No. 1

Owned by MAGNOLL

Texaco, Inc 35-3 W

Farm F.A. Hudson

County Summer
1650' FNL 330'

District El Dorado

Elevatic

e/01

TD. 4801

Rig Commenced
Rig Completed
Drilling Commenced
Drilling Completed
Torpedoed None Qts.

3 17 1951
5 3 1951

Barnett Drilling Inc.

Kind	Put In		Pulled		Left In		
	Ft.	In.	Ft.	In.	Ft.	In.	
8-5/8" OD 32# 8 V. Thd. L.W. Rge. 1 Casing	605	0					Cemented W/400
5-1/2" OD 11# 8 Rd. Thd. H-40 E.W. Range 2	4782	0					Cemented W/500
2-3/8" OD 4.7# 8 Rd. Thd. API EUE H-40 Seamless tubing	4782	0					

Transfer in No. 4642

Our No.

Estimated Oil Production 2036

Bbls.

Gas

Voucher No.

FORMATION	TOP	BOTTOM	
Shale & Red Bed	0	25	
Red Bed	25	47	
Sand	47	85	
Red Bed & Shells	85	140	
Shale, Blue	140	325	
Shale & Shells	325	335	
Shale, Blue Sticky	335	405	
Shale, Blue	405	470	
Shale & Shells	470	602	
Lime	602	605	8-5/8" cas
Lime & Shale	605	870	W/400 sack
Shale & Lime	870	1255	
Lime	1255	1280	
Lime & Shale	1280	1635	
Shale	1635	2070	
Lime & Shale	2070	2810	
Shale & Lime	2810	3235	
Sand, Shale & Shells	3235	3320	
Shale & Lime	3320	3485	
Shale	3485	3592	
Sand	3592	3647	Top of Kan
Lime	3647	3770	
Lime & Shale	3770	3825	
Lime	3825	3870	
Lime & Shale	3870	3985	
Lime	3985	4110	
Shale & Lime	4110	4150	
Lime	4150	4200	
Shale & Lime	4200	4265	
Lime	4265	4305	
Shale	4305	4350	Top of Mi
Lime	4350	4400	
Lime & Chert	4400	4460	
Lime	4460	4690	
Lime & Shale	4690	4745	Top of Kir
Shale	4745	4760	Top of Vic
Lime	4760	4787	Top of Sin
Sand, Simpson Dolomite	4787	4790	5-1/2" cas
Sand, Dolomite	4790	4791	Cemented
Dolomite, Sandy	4791	4793	Cored W/C
Dolomite, Slightly Sandy	4793	4795	4798' KFM
Dolomite, Sandy	4795	4796	
Dolomite, Very sandy	4796	4798	

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1970
CONSERVATION DIVISION
Wichita, Kansas