

R

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sumner County, Sec. 9 Twp. 35 Rge. 3 (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Texaco, Inc.

Lease Name F.A. Hudson Tr. 5, Well #4 Well No. 4

Office Address Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 11/9/70 19

Plugging completed 11/12/70 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hess

Producing formation Depth to top Bottom Total Depth of Well 5064' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	615	none
				5 1/2"	5030'	2710'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 4850' and ran 5 sacks of cement. Shot pipe at 2895', 2805', 2715', pulled 88 joints. Bailed hole to 300', rock bridge, 30 sacks of cement, mudded to 20' and ran 5 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 24th day of November, 1970

My commission expires

2/15/71

Notary Public.



15-191-10235-0001

Q

Record of Well No. 4

Owned by MAGNOLIA PETRO

F. A. HUDSON

Farm Sumner County Kansas State
 District El Dorado, Kansas 330' FSL 330' FWL NE/4 Sec. 9-35-3W

Rig Commenced				
Rig Completed				
Drilling Commenced	Aug.	11	1951	Barnett Drlg., Inc., Wichita, Kan
Drilling Completed	Sept.	25	1951	
Torpedoed	Qts.	None		

Kind	Put In		Pulled		Left In		REMARKS
	Ft.	In.	Ft.	In.	Ft.	In.	
OD 28# 8 V Thd. L.W. - Range 1 Casing	615	0					Cemented w/425 Sacks - Cir
OD 17# 8 Rd. Thd. H-40 Seamless - Range 2	5064	0					Cemented w/250 Sacks
# 8 Rd. Thd. E.U.E. H-40 Smls. Tubing	4831	0					
# 8 Rd. Thd. E.U.E. J-55 Smls. Tubing Range 2							

Transfer in No. 5163-5164 Our No.
 Estimated Oil Production 17 Bbls. Gas Cu Ft.
 Voucher No.

FORMATION	TOP	BOTTOM	REMARKS
Clay	0	40	
Sand	40	50	
Clay & Shale	50	200	
Clay, shale & Red Bed	200	250	
Shale & Shells	250	590	
Shale & Lime	590	615	8-5/8" Csg. Set @ 615
Shale & Shells	615	1040	Cemented w/425 Sacks.
Shale & Lime	1040	1630	
Shale & Shells	1630	1925	
Shale & Lime	1925	2055	
Shale & Shells	2055	2305	
Shale & Lime	2305	2420	
Shale & Shells	2420	2620	
Shale & Lime	2620	3310	
Shale & Shells	3310	3410	
Shale & Lime	3410	3620	
Lime, Shale, Sand	3620	3682	Top Kansas City Lime
Lime	3682	3725	
Lime & Shale	3725	4405	Top Mississippi Lime
Lime	4405	4420	Base Mississippi Lim
Lime, Shale, Chat	4420	4450	
Lime	4450	4490	
Lime & Chat	4490	4515	
Lime	4515	4806	Top Viola Lime 4801
Cored from 4806-4890'			
Viola Lime	4806	4824	Top Simpson Sand 48
Simpson Sand	4824	4890	
Drilled from 4890-5043'			
Simpson Sand	4890	4900	
Lime	4900	5043	Top Arbuckle Lime 50
Cored from 5043-5083'			
Lime	5043	5053	
Lime & Dolomite	5053	5068	5 1/2" Csg. Set @ 5064'
Lime	5068	5083	Cemented w/250 Sacks
Drilled from 5083-5166			
Lime	5083	5115	
Lime & Sand	5115	5145	
Lime	5145	5166	
Total Depth	5166		
Plug Back Depth	5030'		

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 5 1970
 CONSERVATION DIVISION
 Wichita, Kansas