

15-191-01530-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

SUMNER

County, Sec. 8 Twp. 35S Rge. 3W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NE SE

Lease Owner K&E and BOA

Lease Name LUDER Well No. L

Office Address 719 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed k 10-30-58 19

Application for plugging filed 10-30-58 19

Application for plugging approved 10-30-58 19

Plugging commenced 10-30-58 19


Plugging completed 10-30-58 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4854' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	537'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 240' set bridge with 1/2 sx hulls & 15 sx cement. Filled with heavy mud to 40' set solid plug with 1/2 sx hulls & 10 sx cement to base of cellar. Job complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.

Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott, of K & E DRILLING, INC. 719 Union Center, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 1958

My commission expires August 11th, 1962.

Patricia M. Edwards Notary Public.

PLUGGING
FILE SEC 8 T 35 R 3W
BOOK PAGE 143 LINE 8

NOV 7 1958
CONSERVATION DIVISION
Wichita, Kansas
11-7-58

D R I L L E R ' S L O G

OPERATOR:	K & E AND BOA 719 Union Center Wichita 2, Kansas	FARM NAME:	#1 LUDER
CONTR:	K & E DRILLING, INC. 719 Union Center Wichita 2, Kansas	LOCATION:	NW NE SE 8-35S-3W SUMNER CO, KANSAS
CASING:	8-5/8" @ 537' (300 sk)	COMMENCED:	10-11-58
R.T.D.	4854'	COMPLETED:	10-30-58
		ELEVATION:	1159' KB
		PRODUCTION:	D & A

FORMATION RECORD

Surface soil & Clay	140
Shale	370
Shale & Shells	538
Lime & Shale	1665
Shale	1910
Lime & Shale	3385
Shale & Sand	3520
Shale	3655
Shale & Sand	3715
Lime	4165
Shale & Lime	4260
Sand & Shale	4319
Lime	4355
Shale	4382
Mississippi Lime	4737
Shale	4785
Shale & Sand	4823
Lime	4382
Sand	4854
R.T.D.	4854

CERTIFICATION

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Dale Silcott, of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the #1 LUDER well.


Dale Silcott

Subscribed and sworn to before me this 5th day of November, 1958.


Patricia M. Edwards, Notary Public

My commission expires: August 11th, 1962.

RECEIVED
REGISTRATION COMMISSION

NOV 7 1958

PLUGGING
FILE SEC. 8 T. 35 R. 3W.
BOOK PAGE 143 LINE 8

CONSERVATION DIVISION
Wichita, Kansas