


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sumner County, Sec. 8 Twp. 35 Rge. 3 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SW SW NE
Lease Owner Rains & Williamson Oil Co., Inc.
Lease Name Thompson #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/4/79 19
Plugging completed 9/13/79 19
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Barnett
Producing formation Depth to top Bottom Total Depth of Well 4886
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	615	none
				5 1/2"	4876	3617'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Sanded to 4865' and ran 5 sacks cement. Shot pipe at 3799', 3589',
worked pipe loose and pulled 95 joints. Pumped 2 sacks hulls, 4 sacks
mud, 225 sacks 50-50 pos, 2% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1979 9-20-79

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of Sept., 19 79

Margaret Melcher
Notary Public.

My commission expires



15-191-20461-0000

WELL LOG

COMPANY Rains & Williamson Oil Co., Inc.

SEC. 8 T. 35S R. 3W

FARM Thompson

NO. #1

LOC. SW SW NE


RID. NO. 3

TOTAL DEPTH 4886'

COUNTY Sumner
KANSAS

COMM. 4-19-75

COMP. 5-4-75



CONTRACTOR Rains & Williamson Oil Co., Inc.

CASING

20	10		
15		8 - 5/8" @ 615' w/350 sx common, 6% gel	ELEVATION 1164 KB
12	6		3% chloride
13		5 1/2" @ 4876' w/160 sx 50-50 pos mix	PRODUCTION Oil
		15% salt.	

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale & Shells	1372
Shale	1790
Shale & Sand	2305
Shale	2580
Sand & Lime	3020
Lime & Shale	3205
Lime & Sand	3480
Shale & Lime	3737
Lime	4280
Shale	4370
Lime & Chat	4434
Lime	4445
Lime & Chat	4601
Chert	4605
Lime	4757
Lime & Shale	4879
Sand	4886
<u>Rotary Total Depth</u>	<u>4886</u>

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1978

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas
County of Sedgwick } ss:

I, Wilson Rains, President of the Rains & Williamson Oil Company, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the Thompson #1 well.

Wilson Rains
Wilson Rains



Subscribed and sworn to before me this 12th day of May 19 75

Juanita M. Green
NOTARY PUBLIC
Juanita M. Green

My Commission Expires: October 4, 1975