

15-191-00028-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County, Sec. 8 Twp. 35S Rge. (E) 3 (W)

Location as "NE/CNW/SW" or footage from lines SE SW NE

Lease Owner G. C. Cummings

Lease Name Mary Thompson Well No. 1

Office Address 703 Natl. Bk. Commerce Tulsa

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 24 19 55

Application for plugging filed 12:00 p.m. May 23 19

Application for plugging approved " " " " 19


Plugging commenced 6:00 p.m. May 23 19 55

Plugging completed May 24th 19 55

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. G. Buffington

Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4861 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	Water	3713	3987			
Mississippi	Oil & Water	4388	4747			
Simpson Sand	Oil & Water	4850	4861			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with mud from 4861 T.D. to 550 ft. - 35 sacks reg. cement 550 ft. to 480 ft.
Mud 480 ft. to 40 - 15 sacks reg. cement 40 ft. to 10 ft. - Steel cap screwed in top surface casing.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Creighton Drilling Co.

Address Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. L. Cowdrey

703 Natl Bk Commerce, Tulsa
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of June, 19 55

Wapasha Savage
Notary Public.

My commission expires 1-13-58

24-2675-S 2-52-20M
PLUGGING
FILE SEC 8 T 35 R 3W
BOOK PAGE 121 LINE 26

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 - 1955 [6] 7-55
CONSERVATION DIVISION
Wichita, Kansas

C. C. CUMMINGSMary Thompson #1 Well
Sumner County, Kansas

June 3, 1955

Started rigging up, April 27, 1955
Started drilling, April 28, 1955
Drilling completed, May 22, 1955Set 595.16 ft. of 10 3/4" surface
pipe. Cemented with 500 sacks
cement.Drilling Contractor:
Creighton Drilling Company
1804 National Bank of Tulsa Bldg.
Tulsa, OklahomaFORMATIONS

Red bed	0	250	Shale	3543	3694
Shale, red bed	250	315	Sand - Layton	3694	3716
Shale & shells	315	1170	Lime	3716	3793
Sand	1170	1232	Shale & lime	3793	3874
Lime & sand	1232	1375	Lime	3874	4025
Lime, shale	1375	1534	Lime & shale	4025	4316
Lime, shale, shells	1534	1720	Shale	4316	4395
Shale & shells	1720	1905	Chat	4395	4413
Shale, sand	1905	2229	Lime, Mississippi	4413	4423
Lime & shale	2229	2399	Lime	4423	4470
Shale	2399	2420	Lime, Mississippi	4470	4517
Sand, Lime	2420	2492	Lime	4517	4735
Lime	2492	2608	Shale	4735	4755
Sand	2608	2654	Limey shale	4755	4786
Lime & shale	2654	2707	Lime & shale	4786	4833
Lime	2707	2785	Dolomite sand	4833	4855
Lime, shale	2785	3032	Sand	4855	4861 T. D.
Shale & shells	3032	3128			
Shale	3128	3278			
Sand	3278	3349			
Shale & sand	3349	3462			
Shale & shells	3462	3543			

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1955
CONSERVATION DIVISION
Tulsa, Kansas

I hereby certify that the depths shown and formations encountered are a true copy of the daily drilling report prepared by our drillers.

Sworn to before me this 3rd. day of June, 1955.

Creighton Drilling Company

Frances Bards Notary PublicBy R. H. Creighton

My Commission expires: March 19, 1959.

PLUGGING
BOOK SEC 8 T 32 R 3W
PAGE 121 LINE 26