

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Sumner County. Sec. 8 Twp. 35S Rge. 3W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SW NE  
Lease Owner Jim Allison  
Lease Name Thompson "A" Well No. 1  
Office Address 220 West Douglas, Suite 748, Wichita, KS 67202  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed August 23 19 73  
Application for plugging filed August 23 19 73  
Application for plugging approved August 23 19 73  
Plugging commenced August 23 19 73  
Plugging completed August 23 19 73  
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene H. Graham  
Producing formation Depth to top Bottom Total Depth of Well 4866 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	651'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug w/ 1/2 sk hulls & 20 sx @ 240';  
1 sk hulls & 10 sx @ 40';  
2' sx in rathole.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Red Tiger Drilling Company  
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens  
1720 Wichita Plaza, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 7th day of September, 19 73

My commission expires May 24, 1977  
Rita H. Frendle  
Notary Public.



DRILLERS LOG

No. 1 Thompson "A"

CASING RECORD:

COMPANY: Jim Allison

DESCRIPTION:

8-5/8" @ 651'  
w/400 sx cement

CONTRACTOR: Red Tiger Drilling Company

NE SW NE  
8-35S-3W,  
Sumner County,  
Kansas

TOTAL DEPTH: 4866'

COMPLETED: August 23, 1973

ELEVATION: K.B. 1157  
D.F. 1155  
G.L. 1152

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay	0	40	
Shale & Sand	40	275	
Shale	275	648	
Anhydrite	648	652	
Shale & Lime	652	3250	
Lime, Shale & Sand	3250	3465	
Lime	3465	3740	
Lime & Shale	3740	3784	
Lime	3784	3855	
Lime & Shale	3855	4377	
Lime, Shale & chert	4377	4420	
Lime	4420	4560	
Lime & Shale	4560	4780	
Lime, Shale & Chert	4780	4866	

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1973  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens  
Linda H. Dickens

Subscribed and sworn to before me this 7th day of September, 1973.

Rita H. Brendale  
Notary Public

My Commission Expires:

May 24, 1977

