

SP

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All In: _____ in Completely
Make Required: _____ Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sumner County. Sec. 4 Twp. 35 Rge. 3 (SE) (W)

Location as "NE/CNW/SW" or footage from lines: SW SE SE
Lease Owner: Texaco, Inc.
Lease Name: N.J. Peters #3 Well No. _____
Office Address: Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12/7/70 _____ 19____
Plugging completed 12/9/70 _____ 19____
Reason for abandonment of well or producing formation: depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Dewey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4822' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	605'	none
				7"	4816'	2664'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole to 3880' and set 6 sacks of cement. Rigged up on 7".
Shot pipe at 2764', 2672', pulled pipe. Bailed hole to 300' and set 15' rock bridge, ran 35 sacks of cement. Mudded to 25' and ran 10 sacks of cement. Talled pipe.

PLUGGING COMPLETE.


RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: KNIGHT CASING PULLING CO., INC.
Address: CHASE, KANSAS

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

Subscribed and Sworn to before me this 14th day of December, 19 70



Margaret Malcher
Notary Public.

My commission expires 2/15/71

15-191-10225-0000
R

LOG OF WELL

SHEET No. 2

4-35-3W

District Kansas Owner The Texas Co. Farm N. J. Peters Well No. 3

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
Clay & Sand	90				CASING RECORD: 10-3/4" casing set at 605' with 450 sacks cement. 7" casing set at 4816' with 500 sacks cement (250 thru shoe and 250 thru DV tool) ELEVATION: 1128-----KB 1126-----DF 1119-----GL TOPS: Stalnaker-----3127 Layton-----3598 Kansas City-----3638 Marmaton-----3912 Cherokee-----4063 Mississippi-----4318 Kinderhook-----4662 Misener-----4719 Viola-----4733 Simpson-----4748 Simpson Sand-----4788
Shale & Shells	725				
Shale & Lime	1060				
Lime & Shale	1255				
Sandy Lime & Shale	1355				
Lime & Shale	1480				
Shale & Lime	1625				
Shale & Lime Shells	1795				
Shale & Lime	2070				
Lime & Shale Sandy	2215				
Shale & Lime	2455				
Lime & Shale	2600				
Shale & Lime	2960				
Lime & Shale	3011				
Shale & Lime Shells	3121				
Shale & Sand	3242				
Sand & Shale	3331				
Sand	3357				
Lime & Shale	3400				
Shale & Broken Lime	3479				
Shale & Lime	3536				
Shale & Lime Shells	3582				
Shale	3618				
Sand	3645				
Lime	3972				
Lime & Shale	4006				
Lime	4042				
Lime & Shale	4132				
Shale	4170				
Lime & Shale	4235				
Sandy Shale & Lime	4275				
Lime & Shale	4314				
Shale & Sand	4316				
Chat	4338				
Lime	4373				
Lime & Chert	4417				
Lime	4655				
Lime & Shale	4683				
Shale & Lime	4735				
Lime	4748				
Sand	4822				
Total Depth	4822				
PBTD	4811				

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1970
CONSERVATION DIVISION
Wichita, Kansas

Measurement from
to top of casing 8'9"
Top of cement 2780'

