

15-191-10229-0000
SP

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

15-191-10229-00-00

Sumner County, Sec. 4 Twp 35 Rge. 3 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SW SE

Lease Owner Texaco, Inc.

Lease Name N.J. Peters #6 (3011 Creekside #3) Well No. 6

Office Address Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 11/18/70 19

Plugging completed 11/20/70 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hess

Producing formation Depth to top Bottom Total Depth of Well 4812 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	602	none
				7"	4811	2312'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 6 sacks of cement on bottom, welded collar on 7".
Shot pipe at 2480', 2390', 2329', pulled 74 joints of 7".
Bailed hole to 300', set rock bridge and ran 35 sacks of cement. Mudded to 25' and ran 10 sacks of cement to plug well.


PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 - 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) [Signature]
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 70

[Signature]
Notary Public.

My commission expires 2/15/71