

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 191-21,896-0000

LEASE NAME Snowden

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER No. 1

4950 Ft. from S Section Line

3630 Ft. from E Section Line

LEASE OPERATOR Sohio Petroleum Company

SEC. 3 TWP. 35S RGE. 3 ~~XXXX~~(W)

ADDRESS 50 Penn Place, Suite 1100, Okla. City, OK 73118

COUNTY Sumner

PHONE#( 405 ) 848-7571 OPERATORS LICENSE NO. 6854

Date Well Completed P&A 12-14-85

Character of Well D&A

Plugging Commenced 12-13-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-14-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District 2, John Sanders

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation NA Depth to Top NA Bottom NA T.D. 4950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surface	To 733'	Size 8-5/8"	Put in 733'	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RIH with open ended drill pipe to 1248'. Broke circ. with mud. Plug #1 - mixed 45 sacks

60/40 pozmix with 2% gel. Plug #2 with open ended drill pipe @ 781' - mixed 40 sacks 60/40 pozmix with 2% gel. Plug #3 - pushed mud sacks down 60' below grade - mixed 25 sacks 60/40 pozmix w/2% gel. Plugged rathole w/10 sacks 60/40 pozmix w/2% gel. Cut off wellhead 3' below G.L. Weld on I.D. Plate.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services RECEIVED No. 5287

Address Box 428, Hays, Kansas STATE CORPORATION COMMISSION

STATE OF Oklahoma COUNTY OF Oklahoma JAN 3 1986 1-3-86

I, John F. Sindelar, (Employed CONSERVATION DIVISION ~~xxxx operator~~ of above-described well, being first duly sworn on oath, says: That I have personal knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John F. Sindelar

(Address) 50 Penn Place, Suite 1100 Okla. City, OK 73118

SUBSCRIBED AND SWORN TO before me this 3 day of January, 19 86

Cynthia L. Arnold  
 Notary Public

My Commission Expires: 11/19/88