

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: Box 1228, Guymon, Oklahoma 73942

Lease Name Drew "A" Well No. 2

Location C NW SE Sec. 1 Twp. 32 Rge. 40 ~~(E)~~ (W)

County Hodgeman Total Depth 6040'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: None

Plugging Contractor: Daco Lease & Well Service

Address: Borger, Texas License No. 138

Operation Completed: Hour 5:00PM Day 10 22 Month 10 Year 1969

The Above well was plugged as follows:

8 5/8" to 1705' circulated w/ cement. 4 1/2" to 5845' cemented.

Top perforations 5741' Plug bottom w/ 50 sacks cement

Top of cement 5100' Mud 5100' to 800'

Spotted 50 sacks cement 800' to 650' Mud 650' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2112' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eaves
Well Plugging Supervisor

DATE 10/27/69

INV. NO. 717-4