

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

*Authority to Plug issued
Dec 26, 1975.*

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1976

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Colorado Oil Company 79101
Complete Address 415 West 8th St. Suite 300, Amarillo Texas
Lease Name Neuenberg Well No. 1-34
Location C 5 1/2 Sec 34 Twp. 32 Rge. (E) (W) 42
County Marston Total Depth 3505

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent's Casing Pulling

Address Liberal, Kans License No. 511

Operation Completed: Hour 12:00 noon Day 5 Month Feb Year 1976

The above well was plugged as follows:

There was 651' of 8 1/8" surface casing. 5 1/2" casing set to 3501'. Perforations were from 2721' to 3228'. Pumped 250 sacks cement at 2 hulls to Bottom of Well. 2nd plug at 1200' with 30 sacks cement. 3rd plug at 650' with 35 sacks cement. 4th plug at 40' with 15 sacks cement. There was 1200' of 5 1/2" casing salvaged.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Thomas Thomas
Well Plugging Supervisor

DATE 2-6-76

INV. NO. 2711-W