

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 15 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sutton of Panhandle Eastern Pipe Line Co. has this date requested permission to plug the following described well:

Mr. Sutton guarantees payment of the plugging fee.

Operator's full Name: Panhandle Eastern Pipe Line Co.

Complete Address: Box 828 Liberal, Kansas

Lease Name: Howell-Rinshart Well No. #1-23

Location: C NE Sec. 23 Twp. 32 Rge. 39 (W)

County Stevens Total Depth 2712' Oil Well     

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Sutton was instructed to plug the well as follows:

16"-571' Circulated w/cement. 10 3/4"-1620' Circulated w/cement. 7"-2350' Cem.  
Plug back to 2510' Plug bottom w/70 Sax. cement top cement 2000'  
Mud 2000' to 1804' Spotted 50 Sax. cement 1804' to 1604'  
Mud 1604' to 590' Spotted 50 Sax. cement 590' to 500'  
Mud 500' to 30' Sand 30' to 20' 10 Sax. cement 20' to 0'

Very truly yours,

Conservation Division Agent