

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 27 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
10-27-69

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Carson of Cities Service Oil Co. has this date requested permission to plug the following described well:

Mr. Carson guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1228, Guymon, Oklahoma 73942

Lease Name: Drew "A" Well No. 2

Location: C NW SE Sec. 1 Twp. 32 Rge. 40 (E) (W)

County Hodgeman Morton Total Depth 6040' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Carson was instructed to plug the well as follows:

8 5/8" to 1705' circulated w/ cement. 4 1/2" to 5845' cemented.

Top perforations 5741' Plug bottom w/ 50 sacks cement

Top of cement 5100' Mud 5100' to 800'

Spott 50 sacks cement 800' to 650' Mud 650' to 45'

Plug, Hysls & 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Evers  
Conservation Division Agent