

State of Kansas



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
10-22-62  
OCT 22 1962

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date 18 October, 1962, authorized

The following plugging operation:

Operator's full Name: Anadarko Prod. Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Mc/Clure Well No. # D-2

Location 1370' From N/E&So. Linesec. 4 Twp. 32S Rge. 38 (E)(W)

County Stevens Total Depth: 6225'

Oil Well  Gas Well  Input Well  SWD Well

D & A  Other well as hereafter indicated:

Operator was instructed to plug well as follows:

13 3/8" 590' Cemented w/375 sax. 85/8" 1739' Cemented w/100 sax.

Mud 6225' to 2816' Pump 90 sax. cement 2816' to 2400'

Mud 2400' to 707' Pump 45 sax. cement 707' to 572'

Mud 572' to 40' 15 sax. cement 40' to surface.

Very truly yours

*Flugh Scott*

