

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Laird of Mesa has this

date requested permission to plug the following described well:

Mr. Laird guarantees payment of the plugging fee.

Operator's full Name: Mesa Petroleum Co.

Complete Address: Box 2009, Amarillo, Texas

Lease Name: Youngren Well No. 2-10

Location: NE SW SW 1250 FSL & 1250' FWL Sec. 10 Twp. 32 Rge. 39 XB (W)

County: Stevens Total Depth 2546 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole X

Mr. Laird was instructed to plug the well as follows:

8 5/8" to 595' circulated w/ cement. T.D. 2546'

Left 1184' of Drill pipe in Hole. Top of pipe 1362'

Spot 50 sacks cement 1362' to 1200' Mud 1200' to 575'

Spot 35 sacks cement 575' to 475' Mud 475' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent