

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Haggett of Mobil has this

date requested permission to plug the following described well:

Mr. Haggett guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1934, Oklahoma City, Oklahoma

Lease Name: Roach #1 Unit Well No. 2

Location: C nE Sec. 27 Twp. 32 Rge. 38 (E) (W)

County: Stevens Total Depth 3060' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Haggett was instructed to plug the well as follows:

8 5/8" to 602' circulated w/ cement. 5 1/2" to 3059' cemented.

Topperforations 2898' Plug bottom w/ 20 sacks cement.

Topo# cement 2680' Mud 2680' to 600'

Spot 35 sacks cement 600' to 500' Mud 500' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent