

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

22 May 1982

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-189-20,579

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1982
5-25-82
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Jim Barlow of Anadarko Production Co. has this date requested permission to plug the following described well:

Operator's Full Name: Anadarko Production Co.

Complete Address: P.O. Box 351 Liberal Kansas 67901

Lease Name: Walters Well No. A1

Location: C-5E/4 Sec. 13 Twp. 32 Rge. 38 (E) (W)

County: Stevens Total Depth: 6200'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Barlow was instructed to plug the well as follows:

They cement circulated 1753' of 8 1/8" surface casing. 1st plug at 3150' with 2.5 sbx of cement. 2nd plug at 2850' with 5.0 sbx of cement. 3rd plug at 1800' with 6.0 sbx of cement. 4th plug at 780' with 2.5 sbx of cement. 5th plug 40' to 0' on solid bridge with 10 sbx of cement. Then circulated 10 sbx of cement in rat hole & 5 sbx of cement in mouse hole. The cementing was accomplished by Halliburton Co. (over)

Very truly yours,

Paul A. Luthie
Conservation Division Agent

The cement was pumped through drill pipe with
hole full of heavy mud.

Paul A. Luthi