

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Beatty of Anadarko Prod. Co. has this
date requested permission to plug the following described well:

Mr. Beatty guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Smith "C" Well No. 1

Location: G NW 1/4 Sec. 15 Twp. 32 Rge. 38 (E) (W)

County Stevens Total Depth 2892' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole X

Mr. Beatty was instructed to plug the well as follows:

8 5/8" to 609' circulated w/ cement T.D. 2892'

Lost four drill collars & some drill pipe on bottom & hole was abandoned.

Mud 2892' to 660' Spot 35 sacks of cement 660' to 545'

Mud 545' to 45' Plug, hulls & 15 sacks cement 45' to 0'

Weld plate on 8 5/8".

RECEIVED
STATE CORPORATION COMMISSION Very truly yours,

MAY 26 1966

CONSERVATION DIVISION
Wichita, Kansas

Edmund J. Jones
Conservation Division Agent