

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 21 1965

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Gattin of Anadarko Production Co. has this

date requested permission to plug the following described well:

Mr. Gattin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Howell Well No. # B-1

Location: C NW NE Sec. 20 Twp. 32 Rge. 38 (E) (W)

County Stevens Total Depth 3100 Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gattin was instructed to plug the well as follows:


8 5/8"-611' Circulated w/cement. 4 1/2"-3100' Cemented. Top Perforations-2902

2 7/8"-2880' -w/packer. Plug bottom w/140 Sax. cement top cement 2530'

Mud 2530' to 625' Spotted 40 Sax. cement 625' to 500'

Mud 500' to 40' Plug and 15 Sax. cement 40' to 0

Very truly yours,


 Conservation Division Agent