

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1972
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Kuhn of Graves Drlg. Co. Inc. has this
date requested permission to plug the following described well:Mr. Kuhn guarantees payment of the plugging fee.Operator's full Name: Robert E. CampbellComplete Address: 417 S Glendale Wichita, KsLease Name: W.R. Pinkerton A Well No. 1Location: C E/2 NE/SE Sec. 8 Twp. 29S Rge. 6 (E)(W) WCounty: Kingman Total Depth 4122 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Kuhn was instructed to plug the well as follows:223 ft 8 5/8 surface pipe cemented with 200 sacks. Fill
hole to 220 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to
40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

Conservation Division Agent